

Index File No. <u>V 13</u>		CORNER RECORD (SEARCH) (Ref. PSM 7151.4)		Tract or Survey No. _____		Cor. No. _____ Sec. _____	
T <u>13</u> S <u>R. 36</u> E		R.D. <u>Unity</u>		County <u>Baker</u>			
Merid <u>Willamette</u>		N.F. <u>W. W.</u>		State <u>Oregon</u>			
CORNER DIAGRAM T 13 S R 36 E S 28 S 27 N S 33 S 34 CS 1975		DESCRIBE CORNER MONUMENT FOUND A 2½ in. brass cap on a 1 in. iron pipe projecting 9 ins. out of the ground with a surrounding rock mound. Brass cap marked as shown in corner diagram.					
		DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND None					
PHOTO IDENTIFICATION DATA Photo No. <u>EWD-12-124</u> Filed At. _____ Object Ident. _____ Ident. By <u>W.L. Hanley</u> Signature		DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER					
PLANE COORDINATE POSITION DATA State _____ Zone _____ X _____ Y _____ Estab. By _____ Agency							
Signature <u>William L. Hanley</u>		Title <u>ORLS 1639</u>		Division _____		Headquarters _____	
				Date <u>11-2-79</u>		7100-62 (3, 60)	

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set a 6 foot steel fence post 3 ft. north of corner monument and attached a sign 54-4 and a sign 54-2 and improved rock mound.

ACCESSORIES: DESCRIBE NEW B-T-W WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A pine 6 ins. diam. bears N 58° E, 24.4 ft. dist. mkd T 13 S R 36 E S 27 BT
A pine 6 ins. diam. bears S 43° E, 41.0 ft. dist. mkd T 13 S R 36 E S 34 BT
A pine 10 ins. diam. bears S 87° W, 40.8 ft. dist. mkd T 13 S R 36 E S 33 BT
A pine 16 ins. diam. bears N 09° W, 13.0 ft. dist. mkd T 13 S R 36 E S 28 BT
Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

Work Done By W. L. Hanley Title Land Surveyor Date 11-2-79 State Registration No. 1639
or Agency

Certified Cor. Record Prepared XXX No Filed At: _____ Date _____

REMARKS

Witness: Jeff Townsend

Index File No. V 13 T. 13 S R. 36 E W.M. Tract or Surv. No. _____ Cor. Sec. _____

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

FILED July 9, 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 13-36-52