

Index File No. V 15		CORNER RECORD (SEARCH)		Tract or Survey No.		Cor. No. 1/4	
T 13 S R. 36 E		R.D. Unity		County Baker			
Merid. Willamette		N.F. W. W.		State Oregon			
<b>CORNER DIAGRAM</b>  T 13 S R 36 E  1/4 S 27 S 34  CS 1976		<b>DESCRIBE CORNER MONUMENT FOUND</b>  A 2 1/2 in. brass cap on a 1 in. iron pipe projecting 5 ins. out of the ground and marked as shown in the corner diagram.					
		<b>DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND</b>  None					
<b>PHOTO IDENTIFICATION DATA</b> Photo No. EWD- 12-124 Filed At. Object Ident. Ident. By W. L. Hanley Signature		<b>DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER</b>					
<b>PLANE COORDINATE POSITION DATA</b> State _____ Zone _____ X _____ Y _____ Estab. By _____ Agency							
Signature William L. Hanley		Title ORLS 1639	Division	Headquarters	Date 10-30-79	7100-62-13, 681	

### CORNER RECORD (PERPETUATION)

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Attached a sign 54-4 to steel fence post alongside corner monument and improved surrounding rock mound.

**ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

A pine 12 ins. diam. bears S 33° W, 40.0 ft. dist. marked 1/4 S 34 BT  
A pine 12 ins. diam. bears N 57° W, 55.7 ft. dist. marked 1/4 S 27 BT  
Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

Work Done By W. L. Hanley Title Land Surveyor Date 10-30-79 State Registration No. 1639  
Certified Cor. Record Prepared ? Yes No Filed At: Date

#### REMARKS

Witnesses: Jim DeMastus and Jeff Townsend

Index File No. V 15 T. 13 S R. 36 E W.

Tract or Surv. No.

Cor. 1/4

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

William L. Hanley

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

FILED July 9, 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 13-36-57