


T 13 S R. 36 ER.D. UnityCounty BakerMerid. WillametteN.F. W. W.State Oregon

## CORNER DIAGRAM



## DESCRIBE CORNER MONUMENT FOUND

A 2½ in. aluminum cap on a 1 in. iron pipe projecting 3 ins. out of the ground with a steel fence post alongside. Aluminum cap marked as shown in corner diagram.

## DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

## PHOTO IDENTIFICATION DATA

Photo No. not ident.

Filed At: \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

## PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

Title

ORLS 1639

Division

Headquarters

Date

11-2-79

7100-52 (3. 68)

## CORNER RECORD (PERPETUATION)

## MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Attached a sign 54-9 and a sign 54-2 to steel fence post and improved rock mound surrounding the corner monument.

## ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A fir 6 ins. diam. bears N 55° W, 7.9 ft. dist. marked S 1/16 S 28 BT  
A fir 6 ins. diam. bears S 70° E, 22.7 ft. dist. marked S 1/16 S 27 BT

Each new bearing tree has a sign 54-3 attached below a band of red paint and has a brass washer marked LS 1639 nailed flush with BT blaze.

Work Done By W. L. Hanley Title Land Surveyor Date 11-2-79 State Registration No. 1639

Certified Cor. Record Prepared? XXX No Filed At: \_\_\_\_\_

Date \_\_\_\_\_

## REMARKS

Witness: Jeff Townsend

Index File No. U 13 T. 13 S R 36 E W. M.

Tract or Surv. No. \_\_\_\_\_

Cor. 1/16

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

FILED July 9, 1982

BAKER COUNTY SURVEYOR

SURVEY NO. 13-36-58