


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

B-17

History of original corner establishment:

None. No previous history.



Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

Corner position established by survey control...

Set 2½" aluminum pipe with 2½" aluminum cap 20" in the ground and surrounded with a mound of earth and stones. Cap marked as shown in corner diagram.

New bearing trees established:

A ponderosa pine 6" diam bears S29°W, 30.7' marked N1/16S3 BT.

A ponderosa pine 6" diam bears S52°30'E, 71.6' marked N1/16S2 BT.

New bearing trees have a brass washer stamped PLS 1639 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post alongside corner and attached sign 54-9 and 54-2.

Compass declination 19° East.

I hereby certify that the above corner monument was properly established by me and witnessed by Jim DeMastus on November 04, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor..... County of...Baker.....

State of.....Oregon....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 1-23-87

☆ GPO—799-276

BAKER COUNTY SURVEYOR

INDEX NO 13-36-66