

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-13

History of original corner establishment:

Corner established by Henry W. Cooke under Contract No. 528, and dated April 10, 1886.

Surveyor General records state: Set a basalt stone 16 x 12 x 7 ins in ground for cor to secs 3,4,9 10 marked with 5 notches on S and 3 notches on E edges from which: A fir 10" dia bears N40° E, 18 lks dist marked T13SR36ES3 BT. A pine 30" dia bears S20° E, 50 lks dist marked T13SR36ES10 BT. A pine 22" dia bears S45° W, 44 lks dist marked T13SR36ES9 BT. A fir 12" dia bears N80° W, 15 lks dist marked T13SR36ES4 BT.

DIAGRAM

T 13 S R 36 E

S 4 | S 3

S 9 | S 10

1980

RLS 980

Corner re-established by E. Graves in 1980 and his Record states: Set 3" brass cap on 2½" x 30" galvanized pipe and buried 6" in ground with rock mound around pipe to right of ca Buried original stone next to B.C. New bearing trees: 4" p.pine, N36½° W, 37.4' scribed X, BT. 12" p.pine, N13½° E, 42.3' scribed T13SR36ES3 BT. 5" fir S60° E, 14.3' scribed T13SR36ES10 BT. 8" p.pine S80° W, 48.0' scribed T13SR36ES9 BT. All BT's have sign 54-3 & 54-4. Set steel guard post with sign 54-4 along side B.C. Painted red band around BT's. Tagged tree

Description of corner evidence found: with L.S. 980 washer.

Found a 3" brass cap on 3" galvanized iron pipe protruding 12" from stone mound.

A down rotten snag bears N40° E, 18 lks with visible scribing on open blaze (original BT). A 18" down ponderosa pine snag bears S20° E, 33.0' with visible scribing on open blaze (original BT). A 12" ponderosa pine bears N13½° E, 42.3' with scribing visible on partially healed blaze (Graves BT). A 6" fir (bug damaged) bears S60° E, 14.0' with visible scribing on partially healed double blaze (Graves BT). A 7" ponderosa pine bears S80° W, 48.0' with scribing visible on partially healed double blaze (Graves BT). A 6" ponderosa pine bears N36½° W, 37.4' with visible scribing on a partially healed single blaze (Graves BT).

Description of monument and accessories established to perpetuate the original location of this corner

Maintained corner by firming up monument and surrounded it with earth and stone. Set a steel fence post South of corner and attached sign 54-2 and 54-9.

New bearing tree established:

A 14" tamarack bears S64° E, 32.0' scribed T13SR36ES10 BT.

New bearing tree has a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around all Bearing Trees.

Compass declination 19° East.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision and witnessed by Willard Hulick on October 29, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Willard R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the day of ; 19 , at o'clock m., (signed)
..... by
(COUNTY OFFICIAL) (DEPUTY)