

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**History of original corner establishment:**

Corner established by Henry W. Cooke under Contract No. 528, and dated April 10, 1886.

Surveyor General records state:

Set a basalt stone 14 x 12 x 10 ins 10 ins in ground for 1/4 sec cor marked 1/4 on N face and raised a mound of stone alongside.

E-15

**DIAGRAM**

T 13 S R 36 E

$\frac{1}{4}$  S  $\frac{3}{10}$

1986

PLS 1106

**Description of corner evidence found:**

None. Corner area searched for 4 hours with a 2 person crew incluning 1 PLS. Corner falls in a rock patch about 20' South of old E-W fence. Posts were braced with rock mounds. This corner area has been searched by others in the past and many rocks turned over. Utilized ridge call to East for search but it wasn't much help because ridge top is flat.

**Description of monument and accessories I established to perpetuate the original location of this corner**

Re-established corner by single proportion measure between found section corners E and W...

Set 2½" aluminum pipe with 2½" aluminum cap 15" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 8" juniper bears N80½°E, 24.8' scribed 1/4S3 BT.

A 10" ponderosa pine bears S9°W, 27.6' scribed 1/4S10 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post along-side corner and attached sign 54-9.

Compass declination 19° East.

I hereby certify that the above corner monument was properly re-established to U.S.F.S standards under my supervision and witnessed by Willard Hulick on October 29, 1886.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Willard R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of County Surveyor..... County of Baker.....  
State of Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....; 19....., at ..... o'clock .....m., (signed)  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)