

# CERTIFIED RECORD OF LAND CORNER MONUMENTATION

**History of original corner establishment:**

None. Corner never set.

G-15

### DIAGRAM

T 13 S R 36 E

C  $\frac{1}{4}$

2 10

1986

PLS 1106

**Description of corner evidence found:**

None.

Description of monument and accessories I established to perpetuate the original location of this corner

At position established by survey...

Set 2½" aluminum pipe with 2½" aluminum cap 22" in the ground and surrounded with a mound of earth and stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 8" ponderosa pine bears S54°W, 26.1' scribed C1/4S10 BT.

A 9" ponderosa pine bears S17½°W, 28.3' scribed C1/4S10 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 & 54-9 and painted face of blaze and a 6" band around each BT. Set steel fence post South of corner and attached sign 54-9 and 54-2.

Compass declination  $19^{\circ}$  East.

I hereby certify that the above corner monument was properly established to U.S.F.S. standards under my supervision and witnessed by Willard Hulick on October 31, 1986.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

Will R. Well

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Office of County Surveyor ..... County of Baker  
Oregon .....  
 State of ..... , I hereby certify that the within instrument was filed in this office  
 for record on the ..... day of ..... ; 19..... , at ..... o'clock ..... m., (signed)  
 ..... by .....  
 (COUNTY OFFICIAL) (DEPUTY)