


RECORD OF LAND CORNER MONUMENTATION

CORNER: C1/4 Cor. Sec. 31, Twp. 13 S., R. 37 E., W.M.
ORIGINAL SURVEY BY: Not
CONTRACT NUMBER: Previously
CONTRACT DATE: Established




ORIGINAL G.L.O. DESCRIPTION: None, not previously established

EVIDENCE FOUND: None, not previously established

DESCRIPTION OF MONUMENT AND ACCESSORIES SET:
At the corner point I set a 5/8"X30" iron pin with attached 2½" aluminum cap, 27" in the ground. Built a 2 ft. mound of stone around iron pin. The Cap is marked as shown below.

- FROM WHICH, I SET THE FOLLOWING REFERENCE POINTS:
- A 5/8"X30" iron pin bears N.49°28'E., 23.75 ft., with attached yellow plastic cap marked BENCHMARK SURVEYING
 - A 5/8"X30" iron pin bears S.44°47'E., 28.25 ft., with attached yellow plastic cap marked BENCHMARK SURVEYING
 - A 5/8"X30" iron pin bears S.38°14'W., 21.47 ft., with attached yellow plastic cap marked BENCHMARK SURVEYING
 - A 5/8"X30" iron pin bears N.48°14'W., 21.54 Ft., with attached yellow plastic cap marked BENCHMARK SURVEYING



Used RTK GPS to measure Reference Points. Bearings are based on Baker County Survey 13-36-94.

Work Performed BY:
Michael C. Springer, PLS
Thea Ensign, Technician

Benchmark Land Surveying, Inc.
217 N. Canyon Blvd.
John Day, OR, 97845
(541) 620-0676
mike@benchmarkls.com

Surveyed: June 12, 2025



EXPIRES: 6/30/2026

FILED July 8, 2025
BAKER COUNTY SURVEYOR
SURVEY NO. 13-37-45