

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-19

History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract no 427 dated December 15, 1881.

Surveyor General records state:

Set a basalt stone 15 x 12 x 10 ins, 10 ins in ground for 1/4 sec cor marked 1/4 on N face from which:

A fir 20 ins dia bears N25°E, 39 lks dist marked 1/4S BT.

A mahognay 6 ins dia bears S30°W, 19 lks dist marked 1/4S BT.

DIAGRAM

T 14 S R 36 E

$\frac{1}{4}$ $\frac{S}{S}$ $\frac{2}{11}$

1986

ORLS 1639

Description of corner evidence found:

No trace of original stone.

A fir snag 28 ins dia bears N85°E, 32 ft with bark scribe "1/4S2 BT", not an original BT.

A dead mahognay 10 ins dia bears S30°W, 19 lks with scribes "1/4S BT" on open blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by reversed record bearing and distance from sec 11 BT...

Set a 2½" aluminum cap on a 2" aluminum pipe 30" long 25" in the ground with 5" projecting out of the ground with a surrounding rock mound and a 6' fence post alongside with sign 54-9 attached. Cap marked as shown in corner diagram.

The original BT and the fir snag have signs 54-3 and 54-4 attached below a 6 inch band of red paint.

New bearing trees established:

A fir 8 ins dia bears N10°E, 21.6 ft dist marked 1/4S2 BT.

A fir 12 ins dia bears S74°30'W, 26.1 ft dist marked 1/4S11 BT.

Each new BT has a brass washer marked PLS 1639 nailed flush to BT blaze and has signs 54-3 and 54-9 attached below a 6 inch band of red paint.

I hereby certify that the above described corner monument was properly established by me on May 7, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED May 15, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 14-36-14