

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-21


History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract no 427 dated December 15, 1881.

Surveyor General records state:

Set a basalt stone 18 x 12 x 10 ins, 12 ins in ground for cor to secs 11, 12, 13 & 14 marked with 4 notches on S and 1 notch on E edges from which:

A pine 12 ins dia bears N40°E, 77 lks dist marked T14SR36ES12 BT.
 A pine 30 ins dia bears S60°E, 71 lks dist marked T14SR36ES13 BT.
 A mahogany 5 ins dia bears S70°W, 52 lks dist marked T14SR36ES14 BT.
 A pine 40 ins dia bears N20°W, 56 lks dist marked T14SR36ES11 BT.



Description of corner evidence found:

No trace of original basalt stone.

A pine 44 ins dia bears N20°W, 56 lks with fragmentary scribes on open blaze.
 A dead mahogany 6 ins dia bears S70°W, 52 lks with full record scribes on open blaze.
 A windblow pine 30 ins dia bears S60°E, 71 lks with fragmentary scribes on open blaze.
 A windblow pine 16 ins dia bears N40°E, 77 lks dist with fragmentary scribes on open blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by reversed record bearing and distance from secs 11 & 14 BT's...

Set a 2½" aluminum cap on a 2" aluminum pipe 30" long 25" in the ground with 5" projecting out of the ground with a surrounding rock mound and a 6' fence post alongside with sign 54-9 attached. Cap marked as shown in corner diagram.

The original BT's have signs 54-3 and 54-4 attached below a 6 inch band of red paint.


New bearing trees established:

A pine 8 ins dia bears N12°E, 48.5 ft marked T14SR36ES12 BT.
 A fir 20 ins dia bears S84°W, 67.0 ft marked T14SR36ES14 BT.

Each new bearing tree have brass washer marked PLS 1639 nailed flush with BT blaze and have signs 54-3 and 54-9 attached below a 6 inch band of red paint.

No other trees available in healthy condition, therefore marked the SW corner of rock slab 30' x 15' x 5' B X O which bears S85°E, 13.8 ft, painted said corner red and attached signs 54-3 and 54-9.

I hereby certify that the above described corner monument was properly established by me on May 8, 1986.



Office of.....County Surveyor.....County of.....Baker
 State of.....Oregon....., I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED May 15 1986
 BAKER COUNTY SURVEYOR
 SURVEY NO. 14-36-15