

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-25

History of original corner establishment:

Corner established by Eugene P. McCorneck under GLO contract No. 398 dated July 2, 1881.

Surveyor General records state:

Set a basalt stone 14 x 8 x 8 ins, 10 ins in ground for cor to secs 7, 12, 13 & 18 marked with 2 notches on the N and 4 notches on S edges from which:

A fir 14 ins dia bears N60°E, 54 lks dist marked T14SR37ES7 BT.

A fir 12 ins dia bears S65°E, 14 lks dist marked T14SR37ES18 BT.

A pine 14 ins dia bears N85°W, 36 lks dist marked T14SR36ES12 BT.

No other trees within limits, raised mound of stone alongside.

NOTE: Henry W. Cooke, under GLO contract No. 512 dated Aug. 23, 1884, revised this corner to pertain to sections 12 and 13 only dur to inaccuracies found in McCornack's work.

Description of corner evidence found:

No trace of original marked stone.

A fir 26 ins dia bears N69°E, 35.0 ft (record states N60°E, 54 lks) with typical healed double blaze.

A fir 28 ins dia bears S49°E, 7.8 ft (record states S65°E, 14 lks) with healed blaze.

A pine 24 ins dia bears N55°W, 22.5 ft (record states N85°W, 36 lks) with typical healed double blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by locus of face of blazes from original BT's...

Set a 2½" aluminum cap on a 2" aluminum pipe 30" long 25" in the ground with 5" projecting out of the ground with a surrounding rock mound and a 6' fence post alongside with sign 54-9 attached. Cap marked as shown in corner diagram.

The original BT's have signs 54-3 and 54-4 attached belwo a 6 inch band of red paint.

New bearing tree established:

A fir 12 ins dia bears S83°W, 5.0 ft dist marked T14SR36ES13 BT.

New bearing tree has a brass washer marked PLS 1639 nailed flush with BT blaze and signs 54-3 and 54-9 attached below a 6 inch band of red paint.

I hereby certify that the above described corner monument was properly established by me on May 8, 1986.

DIAGRAM

T 14 S	T 14 S
S 12	R 37 E
S 13	S 7
R 36 E	
1986	
ORLS 1639	

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED May 15, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 14-36-16