

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-7

History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract No. 512 dated August 23, 1884.

Surveyor General records state:

Set a basalt stone 30 x 14 x 7 ins, 22 ins in ground for 1/4 sec cor marked 1/4 on N face from which:

A pine 36 ins dia bears N30°E, 76 lks dist marked 1/4S BT.
Dug pits 18 x 18 x 12 ins E & W of cor 5½ ft dist and raised a mound of earth alongside.

DIAGRAM

T 15 S R 37 E

$\frac{1}{4}$ $\frac{S}{S}$
 4 5
 8

1986

ORLS 1639

Description of corner evidence found:

No trace of basalt stone or raised mounds of earth.

A green pine 40 ins dia bears N30°E, 76 lks dist with fragmentary scribes on open blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by reversed record bearing and distance from original BT...

Set a 2½" aluminum cap on a 2" aluminum pipe 30" long 25" in the ground with 5" projecting out of the ground with a surrounding rock mound and a 6' fence post alongside with sign 54-9 attached. Cap marked as shown in corner diagram.

The original BT has signs 54-3 and 54-4 attached below a 6 inch band of red paint.

New bearing tree established:

A juniper 10 ins dia bears S77°W, 80.7 ft dist marked 1/4S8 BT.

New bearing tree has a brass washer marked PLS 1639 nailed flush with BT blaze and signs 54-3 and 54-9 attached below a 6 inch band of red paint.

I hereby certify that the above described corner monument was properly established by me on May 5, 1986.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

FILED May 15, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 14-36-17