

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-9

History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract No. 512 dated August 23, 1884.

Surveyor General records state:

Set a post 4½ ft long 5 ins square with marked stone 24 ins in ground for cor to secs 4, 5, 8 & 9 marked T15S4 on NE, R37E9 on SE, S8 on SW and S5 on NW faces with 5 notches on S and 4 notches on E edges from which:

A pine 16 ins dia bears N15°E, 66 lks dist marked T15SR37ES4 BT.
A pine 50 ins dia bears S64°E, 35 lks dist marked T15SR37ES9 BT.
A pine 40 ins dia bears S12°W, 60 lks dist marked T15SR37ES8 BT.
A pine 20 ins dia bears N20°W, 41 lks dist marked T15SR37ES5 BT.

DIAGRAM

T 15	S	R 37	E
S 5		S 4	
S 8		S 9	
1986			
ORLS 1639			

Description of corner evidence found:

No trace of original post or stone.

A green pine 24 ins dia bears N15°E, 66 lks dist with healed blaze.
A sawed pine stump bears S64°E, 35 lks dist, 50 ins dia with lower blaze.
A sawed pine stump 30 ins dia bears S12°W, 60 lks dist with lower blaze.
A sawed pine stump 20 ins dia with "T" scribe visible, bears N20°W, 41 lks dist.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by reversed record bearing and distance from original BT's...

Set a 2½" aluminum cap on a 2" aluminum pipe 30" long 25" in the ground with 5" projecting out of the ground with a surrounding rock mound and a 6' fence post alongside with sign 54-9 attached. Cap marked as shown in corner diagram.

The original BT and stumps have signs 54-3 and 54-4 attached and a 6 inch band of red paint around.

New bearing trees established:

A fir 6 ins dia bears N31°30'W, 19.0 ft dist marked T15SR37ES5 BT.
A fir 10 ins dia bears S38°30'E, 75.5 ft dist marked T15SR37ES9 BT.
A pine 11 ins dia bears S39°W, 58.3 ft marked T15SR37ES8 BT.

New bearing trees have a brass washer marked PLS 1639 nailed flush with BT blaze and signs 54-3 and 54-9 attached below a 6 inch band of red paint.

I hereby certify that the above described corner monument was properly established by me on May 5, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED May 15, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 14-36-18