

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

L-25

History of original corner establishment:

Corner established by Eugene P. McCornack under GLO contract no. 398 dated July 2, 1881.


Surveyor General records state:

Set basalt stone 14 x 7 x 6 ins, 10 ins in the ground for 1/4 sec cor marked 1/4 on W face form which:

A fir 16 ins dia bears N05°E, 21 lks dist marked 1/4S BT.

A mahogany 7 ins dia bears S86°W, 27 lks dist marked 1/4S BT.

NOTE: Henry W. Cooke, under GLO contract no 512 dated Aug. 23, 1884, revised this corner to pertain to section 13 only due to inaccuracies found in McCornacks' work.



Description of corner evidence found:

No trace of original stone.

A green fir 28 ins dia bears N05°E, 21 lks dist with fully healed blaze.

A live mahogany 9 ins dia bears S86°W, 27 lks dist with fragmentary scribes in open blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position determined by distance intersection from recovered original BT's... Set 2 1/2" aluminum cap on 2" aluminum pipe 30" long 25" in ground with 5" proj. out of ground with a 6' steel fence post alongside with sign 54-9 attached. Cap marked as shown.

The original BT's have signs 54-3 and 54-4 attached below a band of red paint.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision and witnessed by Jim DeMastus on June 26, 1986.



Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....
.....by.....
(COUNTY OFFICIAL) (DEPUTY)

FILED 7-7-81
BAKER COUNTY SURVEYOR
SURVEY NO. 14-36-22