

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Henry W. Cooke under GLO contract no. 512 dated August 23, 1884.

Surveyor General records state:

Set a basalt stone 16 x 12 x 10 ins, 11 ins in ground for 1/4 sec cor marked 1/4 on W face from which:

A pine 30 ins dia bears S60°W, 42 lks dist marked 1/4S BT.

No other trees within limits and raised a mound of stone alongside.

G-21

DIAGRAM

T 14 S R 36 E
1/4
S 11 | S 12
1986
ORLS 1639

Description of corner evidence found:

No trace of original marked stone...corner position falls on fractured rock face.

A green pine 36 ins dia bears S60°W, 42 lks dist with fully healed face.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position determined by distance intersection from recovered original BT's... Set 2½" aluminum cap on 2" aluminum pipe 30" long 12" in ground with 18" proj. out of ground with a 6' steel fence post alongside with sign 54-9 attached. Cap marked as shown.

New bearing trees established:

A pine 9 ins dia bears S27°E, 26.1 ft dist marked 1/4S12 BT and a brass washer marked PLS 1639 nailed flush with BT blaze.

Both new and original bearing trees have signs 54-3 and 54-4 or 54-9 attached below a band of red paint.

I hereby certify that the above corner monument was properly maintained to U.S.F.S. standards under my supervision and witnessed by Jim DeMastus on June 26, 1986.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County Surveyor..... County of..... Baker.....
Oregon

State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)