

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

C-23

History of original corner establishment:

None. Corner was set as part of this survey.

DIAGRAM

T14S R36E

C $\frac{1}{4}$ S1

1987

PLS 1106

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position established...

Set a 2 $\frac{1}{2}$ " x 30" aluminum pipe with a 2 $\frac{1}{2}$ " aluminum cap 24" in the ground and surrounded with a mound of earth and stone.

New bearing trees:

A 11" p pine bears N10°E-30.9' scribed C $\frac{1}{4}$ S1 BT: 1106
A 20" p pine bears S55°E-72.5' scribed C $\frac{1}{4}$ S1 BT: 1106

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post South of corner and attached sign 54-9.

Compass declination 19° East.

This corner was established on July 23, 1987 and witnessed by Bill Blanford.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County Surveyor..... County of...Baker.....
to of...Oregon..... I hereby certify that the within instrument was filed in this office
record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

For 1100-57 (9/71)

FILED 9/28/87
BAKER COUNTY SURVEYOR
SURVEY NO. 100-85-25

GPO-788-276