

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-23

History of original corner establishment:

Corner established by Henry W. Cooke under Contract No 512 and dated August 23, 1884.

Surveyor General records state:

Set a basalt stone 14 x 14 x 8 ins 10 ins in ground for 1/4 Sec cor marked 1/4 on N face from which:

A fir 14" dia brs N30°W, 85 lks dist marked 1/4S BT.
A fir 12" dia brs S60°W, 110 lks dist marked 1/4S BT.

DIAGRAM

T 14 S	R 36
<u>1</u>	<u>S 1</u>
4	S 12
1987	
PLS 1106	

Description of corner evidence found:

No evidence found after 8.0 total hours of search on 3 seperate occasions with 2 person crew incluning 1 PLS.

Description of monument and accessories I established to perpetuate the original location of this corner:

At ~~position~~ on line between the SW & SE corners of Sec 1, at record distance East of Bull Run Creek, etc....

Set 2½" X 30" aluminum pipe with 2½" aluminum cap 24" in the ground surrounded with a mound of earth & stone. Cap marked as shown in corner diagram.

New bearing trees established:

A 10" juniper brs N35½°W, 26.5' scribed 1/4S1 BT.
The 6" south stem of a 3-stem mahogany brs S59°W, 43.7' scribed 1/4S12 BT.

New BT's have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 & 54-9 and painted face of blaze and 6" band of red around each BT. Set 6' steel fence post West of corner and attached sign 54-9.

Compass declination 19° East.

I hereby certify that the above corner monument was properly re-established to U.S.F.S. standards under my supervision and witnessed by Bill Blanford on July 21, 1987.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

CRECOR
JULY 21, 1987
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

26-7100-57 (9/71)

FILED.....
BAKER COUNTY SURVEYOR
SURVEY NO. 14-32-77

GPO-791-311