

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

None. Corner established as part of this survey.

DIAGRAM

T13S R36E
W-W 1/64 $\frac{S36}{S1}$ —
T14S R36E
1987
PLS 1106

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

At position established....

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap, marked as shown in diagram, 18" in the ground and surrounded with a mound of earth and stone.

New bearing trees established:

A 13" ponderosa pine bears S16½°E-29.3' scribed W-W 1/64 S1 BT.
A 18" ponderosa pine bears S77°W-55.7' scribed W-W 1/64 S1 BT.
A 15" ponderosa pine bears N10°W-68.7' scribed W-W 1/64 S36 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post west of corner and attached sign 54-2 and 54-9.

Compass declination 19° East.

This corner was established on September 5, 1987.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County Surveyor..... County of...Baker.....
State of...Oregon....., I hereby certify that the within instrument was filed in this office ;
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)