


T. 14 S., R. 44 E., W. 1 M.

**TRACT DESCRIPTION**

A TRACT OF LAND LYING IN THE NW<sup>1</sup>/<sub>4</sub>SW<sup>1</sup>/<sub>4</sub> OF SECTION 13, T. 14 S., R. 44 E., W. 1 M., DESCRIBED AS FOLLOWS:

BEGINNING N. 13° 50' 25" E., 1,705.26 FEET FROM THE SOUTHWEST CORNER OF THE SAID SECTION 13, AT A POINT WHICH IS THE INTERSECTION OF A BAKER COUNTY ROAD RIGHT OF WAY AND INTERSTATE HIGHWAY NO. 80 RIGHT OF WAY; THENCE FOLLOWING SAID COUNTY ROAD RIGHT OF WAY, N. 42° 42' E., 50 FEET; THENCE S. 47° 01' E., 30 FEET; THENCE S. 42° 42' W., 50 FEET; THENCE N. 47° 01' W., 30 FEET TO THE POINT OF BEGINNING.  
 BEARINGS ARE BASED ON THE OREGON COORDINATE SYSTEM, NORTH ZONE.

FILED April 26, 1968  
 BAKER COUNTY SURVEYOR  
 SURVEY NO. 14-44-2



|  |               |
|--|---------------|
| PROPERTY SURVEY FOR EL PASO<br>NATURAL GAS COMPANY |               |
| HUNTINGTON METER<br>STATION                        |               |
| Baker County                                       | Oregon        |
| JAMES D. HANLEY, ENGINEER<br>BAKER, OREGON         |               |
| APRIL 11, 1968                                     | SCALE 1"=200' |

Found, hwy. monument (N. 47° 01' W., 76.32 bet. mans.)  
Set

Found hwy. mon.  
Set

Note: Pins set are 3/4" x 30" rebar.