



LEGEND

- Set 5/8" x 30" rebar
- Found 1/2" rebar
- () Street names () are original platted names.

CO. RD.
(STATE TAX MAP)

Found, brass disc monument
To 6th St. E. monument (A 1" iron pin.)

NARRATIVE

Monumentation was recovered at the intersections of the following streets: 1st (Johnson) and Monroe, 1st (Johnson) and Washington, 6th (Harrison) and Washington, 6th (Harrison) and Monroe.

Method of proportionate measurements were employed to ascertain locations of street intersections within this area. The centerline of Madison Street was then projected westerly the plat distance of 340 feet to the line marking the western boundary of Blocks 26 and 45, and the northerly half of Block 45 was monumented accordingly with 5/8-inch x 30-inch rebars.

MAP OF SURVEY
IN BLOCK 45, HUNTINGTON TOWNSITE

For the City of Huntington, Oregon
Surveyed June 4, 1981
Scale: 1" = 100'

PROCESSED
PEOPLE'S SERVICE
LOCAL SURVEYORS

James D. Hawley
JAMES D. HAWLEY
1981

FILED 8-19-81

BAKER COUNTY SURVEYOR
SURVEY NO. 17-4-12