

14-44-16

BASIS OF BEARING IS 1ST STREET  
BETWEEN POINTS "A" AND "D"

"B" IS N. 85° 29' 37" E., 2659.48 FROM "A"



### NARRATIVE

THE PURPOSE OF THIS SURVEY FOR THE CITY OF HUNTINGTON IS TO MARK ON THE GROUND CERTAIN LOT CORNERS AS SHOWN HEREON. THE ORIGINAL MAP OF HUNTINGTON IS FILED IN PLAT BOOK NO. 1, PAGE 48, DATED APRIL 8, 1886. THIS PLAT DESCRIBES FOUR "PERMANENT CORNERS" HAVING BEEN ESTABLISHED AT POINTS "A", "B", "C" AND "D". THE MONUMENTATION FOUND AT POINTS "B" AND "C" IS AS DESCRIBED ON THE PLAT. ORIGINAL MONUMENTS AT POINTS "A" AND "D" ARE DESCRIBED AS BOTH BEING "FISH PLATES". IN 1936 OREGON STATE HIGHWAY DEPARTMENT ESTABLISHED A BRASS CAP MONUMENT AT POINT "D" AND AT A POINT 40 FEET NORTHERLY OF POINT "A", BEING AN EXTENSION OF THE LINE BETWEEN POINTS "A" AND "D". DURING THIS SURVEY THE O. S. - H. D. BRASS CAP AT POINT "D" WAS FOUND AS WAS A 5/8 REBAR AT POINT "A"; THE 40 FOOT REFERENCE MONUMENT WAS NOT RECOVERED.

### LEGEND

- FOUND MONUMENT AS NOTED
- SET 5/8" x 30" REBAR WITH PLASTIC CAP MKD "HANLEY ENGRG PLS 1206"
- ( ) RECORD PLAT DISTANCE

## MAP OF SURVEY

IN BLOCKS 5 AND 20, HUNTINGTON TOWNSITE  
FOR CITY OF HUNTINGTON  
SURVEYED JULY 18, 1995

HANLEY ENGINEERING  
BAKER CITY, OREGON

SCALE 1" = 100'

FILED 8-16-95

BAKER COUNTY SURVEYOR

SURVEY NO. 14-44-16

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

James D. Hanley  
OREGON  
SEPTEMBER 23, 1977  
JAMES D. HANLEY  
1206

RENEWAL DATE JAN 1, 1996