


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

T. 14 S., R. 44 E.

J - 19

RECOVERED BY	COORDINATE SYSTEM, ZONE, & UNIT	
Matthew Faulkner, Oregon PLS	United States/NAD83, Oregon North 3601, International foot	
GCDB ID	NORTHING	EASTING
540500	269,051.31	9,039,685.95
LATITUDE	LONGITUDE	
N44°21'32.737"	W117°17'48.347"	



RECORD OF ORIGINAL CORNER AND SUBSEQUENT HISTORY:

Record No. 1: The 1/4 sec. cor. of secs. 11 and 14, T. 14 S., R. 44 E., was established and described in the original field notes of the subdivisional lines T. 14 S., R. 44 E., Willamette Meridian, Oregon, executed by U.S. Deputy Surveyor Henry W. Cooke in 1882 under Contract Number 427.

Description: Set a basalt stone, 20x15x9 ins., 15 ins. in the ground, for 1/4 sec. cor., marked 1/4 on N. face and raised stone mound alongside.

Record No. 2: This same corner was recovered, perpetuated, and held as a controlling monument on a record of survey titled "Map of Survey Section 14, T. 14 S., R. 44 E., W.M., Baker County, Oregon Huntington Site Surveyed June 16 thru August 25, 2004 for RCC Holdings, Inc." on file with the Baker County Land Surveyor's Office, by Thomas J. Hanley, Oregon Professional Land Surveyor No. 1817, recorded on September 7, 2004, Survey Instrument No. 14-44-0032.

Description: North 1/4 Corner, Section 14. Found 16"x9"x8" stone, marked 1/4 on North face, with a mound of stone. Set 2 1/2" brass cap monument.

DESCRIPTION OF CORNER EVIDENCE FOUND AND DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE THE LOCATION OF THIS CORNER:

Recovery Date: 08/27/2023

Description: The 1/4 sec. cor. of secs. 11 and 14, monumented with a galvanized pipe, 1 1/2 ins. diam., firmly set flush with the top of a mound of stone, 3 1/2 ft. base, 1 ft. high, with brass cap, 2 1/2 ins. diam., mkd. as shown below on this corner record, with the original basalt stone, 20x15x9 ins., firmly set on the S. edge of the galvanized pipe, mkd. 1/4 on the N. face, with a steel fence post, E. of the galvanized pipe, approximately 1 ft. dist. in the mound of stone.

Added stones to the mound of stone to now make it flush with the top of the brass cap.

Set a carsonite post, W. of the mound of stone, approximately 4 ft. dist. from the galvanized pipe.

FILED January 29, 2025
BAKER COUNTY SURVEYOR
SURVEY NO. 14-44-45

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Photo of brass cap markings.



Photo of the galvanized pipe monument, firmly set flush with the top of a mound of stone, 3 1/2 ft. base, 1 ft. high.



BAKER COUNTY SURVEYOR	
Date Received _____	
Date Filed <u>January 29, 2025</u>	
By _____	
File No. <u>14-44-45</u>	

REGISTERED PROFESSIONAL LAND SURVEYOR
--

OREGON JUNE 08, 2009 MATTHEW J. FAULKNER 75618LS

RENEWES: 12/31/25