



SURVEY NARRATIVE

The purpose of this survey for Herbert and Laura Keyser and Dorothy Jensen is to mark on the ground the four corners of Lot 8 in Block 42 Huntington Townsite. Controlling monumentation was recovered as shown and proportionate measurement method employed to determine property corner locations.

The original Map of Huntington is filed in Plat Book No. 1 Page 48, dated April 8, 1886. This plat describes four "Permanent Corners having been established at points "A", "B", "C", and "D". The monumentation found at points "B" and "C" is as described on the plat. Original monuments at points "A" and "D" are described as both being "fish plates". In 1936 Oregon State Highway Department established a brass cap monument at point "D" and at a point 40 feet northerly of point "A", being an extension of the line between points "A" and "D". During this survey the O.S.H.D. brass cap at point "D" was found as was a 5/8" rebar at point "A", the 40 foot reference monument was not recovered.

LEGEND

- Found monument as described
- Set 5/8"x 30" rebar with plastic cap marked "HANLEY ENGR. PLS 1206"
- Set 5/8"x 30" rebar w/plastic cap mkd. "HANLEY ENGR. PLS 1206" as a reference monument. Rebar is set on the extended westerly line of Lot 8, a distance of 5.00 feet from the corner point.

() Huntington Townsite Plat data

**MAP OF SURVEY
LOT 8, BLOCK 42
HUNTINGTON TOWNSITE**

FOR
Herbert & Laura Keyser and
Dorothy Jensen
November 10, 1992

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley

OREGON
SEPTEMBER 23 1977
JAMES D. HANLEY
1206

HANLEY ENGINEERING
2043 MAIN STREET
BAKER CITY, OREGON

FILED Dec. 4, 1992
BAKER COUNTY SURVEYOR
SURVEY NO. 19-45-12