



SURVEYOR'S NARRATIVE

THIS SURVEY WAS PERFORMED FOR SPENCER B. GROSS AND COMPANY IN SEPTEMBER OF 1997. FIVE PHOTO-CONTROL PANELS WERE SET AND MONUMENTED AS SHOWN HEREON. POSITIONS WERE DETERMINED USING TWO TRIMBLE 4000ssi RECEIVERS. ALL BASELINES WERE PROCESSED USING STATIC SURVEY, CARRIER PHASE MEASUREMENTS AND TRIMBLE'S GP SURVEY AND WAVE PROCESSOR SOFTWARE. DATA SHOWN IS NAD 1927 HORIZONTAL DATUM AS REQUESTED BY CLIENT. BEARINGS ARE OREGON NORTH STATE PLANE COORDINATE 1927 GRID. DISTANCES ARE IN METERS.

THIS SURVEY IS FILED TO CONFORM WITH O.R.S. 209.250(5)

REGISTERED PROFESSIONAL LAND SURVEYOR
A. McLenon
 OREGON
 JAN. 21, 1992
 HARMON E. MCLENDON
 2537
 renews 12/31/98

FILED NOV. 24, 1997
 BAKER COUNTY SURVEYOR
 SURVEY NO. 14-45-18

G.P.S. CONTROL SURVEY		
SEC.3, T14S, R40E; SEC.6, T14S, R42E; SEC.18, T14S, R45E; SEC.24, T12S, R42E; SEC.6, T11S, R45E; SEC. 8, T11S, R46E; MALHEUR AND BAKER COUNTIES, OREGON		
SPENCER B. GROSS		
SCALE: 1 : 2000		SHEET 1/1
DATE: NOV. 1997		ENGINEERING • SURVEYING • MATERIALS TESTING LA GRANDE, OR. WALLA WALLA, WA. BAKER CITY, OR.
JOB NO. 2719-20		

LEGEND

- Indicates a 5/8" iron rod with a 2" aluminum cap stamped "APA"
- Indicates geodetic control station described hereon.