

**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

**History of original corner establishment:**

Corner established by John Hagel, U.S. Deputy Mineral Surveyor, under instructions received from the United States Surveyor General for Oregon dated Oct. 19, 1899, and designated as Survey No. 378.

T 9 S R 37 E  
MS 378  
1 CH

Surveyor General records state:

Beginning at Cor. No. 1, set a white fir post, 4 ins. square, 4 1/2 ft. long, 18 ins. in the ground with a mound of earth around it, marked Charl. C. 1-378.

CHARLESTON  
Cor. 1

A white fir tree, 20 ins. in diam., bears S40°30'W, 38.0 ft. blazed and marked Charl. C. 1-378 BT.

Corner was remonumented by: John R. Mitchell, an unlicensed Forester, as described by USFS Corner Card, dated 6/1/81.

Record states:

36" WF brs S40 1/2° W, 38' w/ scribing in opened blaze.

Set a 2 1/2" BC on 1" x 32" gal pipe, set 24" deep at cor. pt. in md of stone & earth, marked CH C1 MS 378 JRM 1981.

10" WF brs S61°W, 22'

6" WF brs S51°E 11 1/2', both marked CH 1 MS 378 BT.

Corner was perpetuated by: Leland Myers, per Baker County Survey 8-37-135/9-37-279 in 2003. No Corner Record for this Monument was found. It is apparent Myers accepted the Mitchell brass cap and stamped his number and date over the top of Mitchell's.

**Description of corner evidence found:**

\*Mis-stamped "T8S"

A 1 inch galv. iron pipe with a 2 1/2 inch brass cap, marked as shown. Firmly set 6 inches above ground, with a rock collar.

T8S R37E  
MS 378  
CH1/  
2003  
PLS 699

From which:

A 36 inch white fir (by Hagel) with visible scribe marks on cut open blaze, bears S40 1/2°W, 38.0 ft. to blaze face, 39.6 ft. to a 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive & healthy.

A 9 inch white fir (by Mitchell) with healed blaze, bears S51°E, 11.5 ft to 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive with dead top.

A 14 inch white fir (by Mitchell) with healed blaze, bears S61°W, 22.1 ft to 1 1/2 inch SS washer mkd: PLS 699 in left side center, alive & healthy.

Monument falls West 0.25 miles from Fruit Creek Road; approximately 3,000 feet northerly of the intersection with NF-5540 Road.

**Description of monument and accessories I established to perpetuate original location of this corner:**

Added Bearing Tree and Land Survey Monument signs as needed.

NAD 83 Geodetic Position

Lat. 44°49'02.2" N  
Long. 118°12'53.0" W

Established by: Garmin ETREX 32x

I hereby certify that the corner is monumented and accessories taken as described using a steel tape and a Warren Knight staff compass, set with a declination of 14° East.

Witnesses: David Quittschreiber, Justin Seal

September 21, 2023

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Kristina Powell*

OREGON  
MAY 9, 2017  
KRISTINA POWELL  
91201

EXPIRES 12-31-24

FILED January 8, 2024  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-37-395